

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

*Dickinson*

| FOR CORNERS OF--:                         | LOCATED IN--:   | CORNER CODE NUMBER |
|---|---|--------------------|
| 1. PUBLIC LAND SURVEY_____                | T. <u>41</u> N. <del>XX</del> R. <u>29</u> <del>XX</del> W. | <u>A8 and A9</u>   |
| 2. PROPERTY CONTROLLING IN SECTION_____   | , T. _____ N. S., R. _____ E. W.                            | _____              |
| 3. MISCELLANEOUS PROPERTY IN SECTION_____ | , T. _____ N. S., R. _____ E. W.                            | _____              |
| 4. LOT NO. _____, RECORDED PLAT _____     |   |                    |
| 5. PRIVATE CLAIMS _____                   |   |                    |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Original posts or their accessories not found. Corner A8 had previously been monumented by B. D. Buckler in 1955, but no record of the witnesses was filed; the monument was subsequently removed during logging operations, necessitating re-establishment of the section line. No monument was found at Corner A9, which had been witnessed also by Buckler on July 28, 1955, as previously set from original BT's by Wm. Johnson of the Dickinson County Road Commission; monument probably pulled out by road grader.**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner A8: Re-established 9/10/73 on line between section corners 39.925 ch. to N and to S.**

**Corner A9: Re-established 9/4/73 by reference to NBT's recorded by Buckler on 7/28/55, as follows: Aspen 8 S71°E 59 lks. (Cut down; stump remains)  
Y. Birch 7 N85°W 90 lks.**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner A8: 1" I.D. x 36" iron pipe with 4" brass cap.  
W. Birch 6 S71°E (mag.) 39.2 ft. "1/4S, NBT"  
Spruce 8 N81°W (mag.) 21.3 ft. "1/4S, NBT"**

**Corner A9: 1" I.D. x 20" iron pipe with 4" aluminum cap, buried in road.  
Sugar Maple 5 S75°E (mag.) 42.6 ft. "S30, NBT"  
Y. Birch 6 N55°E (mag.) 62.3 ft. "S19, NBT"**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE January 30, 1974  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

