

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 41 N.R. 29 W


Dickinson COUNTY

DESCRIPTION OF CORNER 1/4 corner for sections 32-33

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 9-26-61

WITNESSES TO CORNER..... 9" soft maple (1/4 S NBT) S 82°E 57 links



8" Cedar " " N 48°W 69 links

Corner lies 3 3/4 chains south of road.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established midway and on line between two section corners. No evidence of original corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE March 13, 1962  
REGISTERED LAND SURVEYOR  
Billy D. Buckler