

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 41 N. R. 29W


Dickinson COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Sections 33-34

CORNER MONUMENT X mark chiseled on rock ledge. 1" Pipe with 4" Brass Cap 2 links south of corner.

DATE MONUMENT PLACED AND WITNESSED 10-10-61 with Ewart Muller, Jr., Iron Mountain, Mich.

WITNESSES TO CORNER..... 8" Soft Maple (1/8 S NBT) N 28° E 63 1/2 links



7" Hard Maple (1/8 S NBT) S 40° E 82 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established on line between two Section Corners and at 40.00 chains from South Section Corner. The North 1/2 mile is short because of error in measuring in the original survey.

Note: Pipe is 2 links South of Actual Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE January 3, 1962
REGISTERED LAND SURVEYOR
Billy D. Buckler