

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 41 N. R. 29W


Dickinson COUNTY

DESCRIPTION OF CORNER South 1/16 Corner bet. Secs. 19-20.

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 10-3-63 with H. S. Peterson, D.F.

WITNESSES TO CORNER..... 9" W. Birch (B.T.) S. 33° E., 21 lks.



10" W. Birch (B.T.) S. 61° W., 22½ lks.

North Corner of foundation, South 44 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was placed midway and on line bet. Sec. Cor. to South and ¼ Cor. to North. Found a small Iron pipe set on the random line at our temporary chaining marker. (1956). Found W. Birch. S. 61° W., 22½ lks. which was squared as a corner previous to 1956.

SURVEYOR'S SEAL

SIGNED Billy O. Buckler DATE 3/5/65
REGISTERED LAND SURVEYOR