

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 41 N.R. 29


Dickinson COUNTY

DESCRIPTION OF CORNER $\frac{1}{4}$ Corner for Sections 22 and 23.

CORNER MONUMENT 1" Iron pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 4-5-63

WITNESSES TO CORNER..... 6" Spruce ($\frac{1}{4}$ S.) (N.B.T.) N. 10° W., 29 $\frac{1}{2}$ lks.



8" Cedar ($\frac{1}{4}$ S.) (N.B.T.) S. 72° E., 81 $\frac{1}{2}$ lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was placed by proportionate distance and on line bet.
a section corner $\frac{1}{2}$ mile to North and line tree approx. 11 $\frac{1}{2}$ Chs. to
South.

SURVEYOR'S SEAL

SIGNED Billy D. Buckles DATE 10/10/63
REGISTERED LAND SURVEYOR