

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 41 NR. 29W

Dickinson COUNTY

DESCRIPTION OF CORNER Sec. Cor. for Secs: 14-15-22-23

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 8" Cedar (S15 NBT) N45°W

8" Cedar (S23 NBT) S5°E

10" W. Pine (S14 NBT) N79°E

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established from line tree 29.25 chs. west; ~~Top~~ line 2 miles east;
sec. cor. 1 mile north and line tree 51.44 chs. south. Swamp edge 2.00
chs. north checks with Gov't Field notes. Cor. lies in old logging road.
Found 28" W. Pine stub blazed years ago at cor. Cor. placed and wit.
4/23/59 with H. S. Peterson, D.F. and N. Spherhake, Marquette.

SURVEYORS SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler DATE 8/21/59
REGISTERED LAND SURVEYOR