

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 41 NR. 29W.

Dickinson COUNTY

DESCRIPTION OF CORNER 1/4 Cor. for Secs: 14-15.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 10" Tamarack (1/4s NBT) S76°E 20 Lks.

9" Cedar (1/4s NBT) S26°W 40 Lks.

7" Cedar (1/4s NBT) N34°E 36 Lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established midway and on line between two sec. cors. Position agrees with swamp edges to north 5.00 chs. and south 3.00 chs. Found green Cedar tree bearing N54°E 18 Lks. This tree has been blazed over 100 years ago. Found no evidence of original B. Ts. Cor. placed and wit. 4/23/59 with H. S. Peterson, D. F. and N. Sperhake, Marquette.

SURVEYORS SEAL

SIGNED *Billy D. Buckler*  
Billy D. Buckler DATE 8/21/59  
REGISTERED LAND SURVEYOR