

✓

**MICHIGAN**  
**DEPARTMENT OF CONSERVATION**  
**FORESTRY DIVISION**

**LAND CORNER RECORD**

T. 41 NR. 29W

----- Dickinson ----- COUNTY

DESCRIPTION OF CORNER 1/4 Cor. for Secs: 15-22 -----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap -----

WITNESSES TO CORNER 6" Aspen (1/4s NBT) N48°E 33 Lks. -----

8" Aspen (1/4s NBT) N80°W 12 Lks. -----

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

Re-established midway and on line between two sec. cors. No evidence of original bearing trees. Cor. lies 2 chs. north of road. Cor. placed and wit. 4/23/59 with H. S. Peterson, D.F. and N. Sperhake, Marquette.

**SURVEYORS SEAL**

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 8/21/59  
REGISTERED LAND SURVEYOR -----