

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 41. NR. 29. W.

Dickinson COUNTY

DESCRIPTION OF CORNER Section corner common to Section 8,9,16,17

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 8" Cedar (S 8 NBT) N 22° W 28 Links

5" Tamarack (S 9 NBT) N 32° E 46 Links

7" Tamarack (S 16 NBT) S 58° E 30 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was replaced at old wood post. Found blazes north, south and west from corner. No evidence of original bearing trees. Distance checks west to stream and east to ridge.

Corner was placed and witnessed September 24, 1959 with Frank J. Bray.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 4/29/60
REGISTERED LAND SURVEYOR
Billy D. Buckler