

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD ✓

T. 41 NR. 29 W

Dickinson COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 7, 8, 17, 18

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 20" Y. Pine (S 18 NBT) S 13° W 15 Links

18" W. Pine (S 17 NBT) S 83° E 20 1/2 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by double proportionate measurement, section corners 1 mile to north, west and east and two miles to south.

Corner was placed and witnessed August 22, 1960.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 8-29-60
REGISTERED LAND SURVEYOR
Billy D. Buckler