

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD ✓

T. 41. NR 29-30. W.

D i c k i n s o n COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 7, 18, 12, 13.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 6" W. Birch (S 7 NBT) N 34° E 32 Links

7" W. Birch (S 18 NBT) S 37° E 72 1/2 Links

4" W. Birch (S 13 NBT) S 89° W 35 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by double proportionate measurements.

Section corners 1 mile to south and west and two miles to east and north, to stream. No evidence of original corner.

Corner was placed and witnessed August 22, 1960.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 8-29-60  
REGISTERED LAND SURVEYOR  
Billy D. Buckler