

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 41 N. R. 29W


Dickinson COUNTY

DESCRIPTION OF CORNER Section Corner common to 17-18-19-20

CORNER MONUMENT 1" Pipe with 4" BrassCap.

DATE MONUMENT PLACED AND WITNESSED 4-18-61

WITNESSES TO CORNER..... 12" Red Oak (clump) (S20 NBT) S 44° E 20½ links



6" Soft Maple (S17 NBT) N 77° E 49 links

8" Jack Pine (S18 NBT) N 56° W 55 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by double proportionate measure from Corners 1 mile South; 1 mile West; 2 miles North and 1½ miles East.
No evidence of original Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE January 30, 1962
REGISTERED LAND SURVEYOR
Billy D. Buckler