

JAN 16 1956

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 41. NR 29. W. . .

Dickinson

COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 27, 28, 33, 34.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap.

WITNESSES TO CORNER 14" Red Pine S 57° E 17 Links.

14" White Pine N 47° W 21 Links.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner set by Proportionate Measure South and West to Lake shore and North to Swamp edge. Two old turnouts (probable B.T.s.)
There is an old line blazed North and South from this point.

Corner placed and witnessed August 31, 1955.

SURVEYORS SEAL

SIGNED

Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE

1/12/56