

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 41. NR. 29 W. .

_____ Dickinson _____ COUNTY

DESCRIPTION OF CORNER 1/4 Section Corner between Sections 16 and 21. . . .

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap.

WITNESSES TO CORNER 12" White Pine N 45° E 79 links

10" Tamarack S 68° E 55 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replace 1/4 Corner from White Pine and Cedar B.T.'s in place, poor condition.

Evidence of stake in soil.

Corner found by chaining with hand compass from 1/2 mile east.

Corner on high ground, swamp 1 ch. south.

Corner placed and witnessed January 27, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 2/14/56
REGISTERED LAND SURVEYOR