

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 41. NR. 29. W. . .

----- Dickinson -----

----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sec. 's 20-21-28-29 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 13" Y. Birch S 5° E 53 links -----

12" Soft Maple N 18° W 33 links -----

8" Soft Maple N 56° E 60 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced section corner from two hemlock stump bottoms (probable B.T.s) bearing N 5° W 14 links and S 15° E 12 links.

Distance checks well to stream bed 4.00 chs. north, lake to east and to corners south and west.

Placed location poster 1 ch. east on road.

SURVEYORS SEAL

SIGNED Billy D. Luckles DATE 8/1/57
REGISTERED LAND SURVEYOR