

✓

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 41 NR 29 W

----- Dickinson -----

----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 19-20-29-30  
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap  
WITNESSES TO CORNER 8" W. Pine S 48° E 94 links  
8" W. Birch N 41° W 69½ links  
-----  
-----

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

Replaced section corner. Found old wood post which checks to good corners in three directions.

Distance checks to streams north and west and to good corners south and east. No evidence of original B.T.s.

Corner lies at the northwest corner of a rock outcrop.

Found by Forestry Division Survey Crew.

**SURVEYORS SEAL**

SIGNED Billy D. Buckler DATE 8/1/57  
REGISTERED LAND SURVEYOR