

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Dickinson

(County)	Located In:	Corner Code -#
1. Public Land Survey	T 41N R 29W	C5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	10		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on September 01, 1992, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C5) Section corner common to Sections 7-8-18-17. Established by U.S. Deputy Surveyor John Burt, 1849. Original BTs: N. Pine 18 S71W 26, N. Pine 10 N05E 15. Corner filed in Dickinson Co. Rd. Commission records by Billy D. Buckler in 1960 as follows: 1" pipe with 4" brass cap set by double proportionate measure between section corners 1 mile to north, west, and east, and two miles to south. 20" Y. Pine (S 18 NBT) S13W 15 L., 18" N. Pine (S 17 NBT) S83E 20.5 L.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C5) Found and accepted 1" pipe with 4" brass Michigan Dept. of Conservation cap. Buckler's NBTs were not recovered. Marked 4 new bearing trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C5) 1" pipe with 4" brass cap.
 7" N. Pine N51W 57.5' (S7 NBT)
 12" N. Pine S67W 58.6' (S18 NBT)
 7" R. Pine S35W 61.3' (S18 NBT)
 3" Cherry S42E 7.4' (S17 NBT)



Signed by Stephan J. Szyszkoski Date 1-26-93
 Surveyor's Michigan License No. 33986