

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Dickinson</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 41N R 29W	M13
	T 41N R 29W	K8
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sep 09 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(M13) Southeast corner of T41N-R29W. Corner recorded in 1956 by Billy D. Buckler: "Sec. Corner has been renewed by unknown surveyor. Possible Cedar B.T. in proper place. Corner placed and witnessed July 26, 1955. Description of corner monument: 1" pipe with 4" brass cap. Witnesses to corner: 9" Aspen N58W 9 links, 7" Balsam N74E 26 links."

(K8) Quarter corner common to Sections 23-24. Corner recorded in 1960 by Billy D. Buckler, RLS: "This corner was reestablished midway and on line between two Section Corners. No evidence of original corner. Corner was placed and witnessed October 2, 1959. Description of corner monument: 1" pipe with 4" brass cap. Witnesses to corner: 18" W. Pine N11W 21 links, 16" W. Pine N53E 23 links."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M13) Recovered the 1955 monument as described, a 1" ID iron pipe capped with a 4" dia. brass Michigan Dept. of Conservation tablet, appropriately stamped, in good condition. The 1955 witnesses were not recovered. Left the monument in place and marked four new bearing trees as described below. Corner recovered and re-witnessed by B.Wheeler and D.Lampela, Baraga District Office.

(K8) Recovered the 1959 monument as described, a 1" ID iron pipe capped with a 4" dia. brass Michigan Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1959 witnesses. The W.Pine NW is dead but standing. The W.Pine NE is in good condition. Left the monument in place and marked new witnesses as described below. Corner recovered and re-witnessed by B.Wheeler and D.Lampela, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M13) Found 1" pipe with 4" brass cap.

Blazed and scribed the following:

16" Cedar N59W 55.9' "S36 NBT"

4" Aspen N19E 16.6' "S31 NBT"

3" Aspen S83E 7.1' "S3 NBT"

4" Aspen S23W 11.9' "S3 NBT"

Bearings are magnetic. Distances are to notch in lower blaze.

(K8) Found 1" pipe with 4" brass cap.

Blazed and scribed the following:

W. Pine S58E 44.8' "1/4S NBT"

10" W. Pine S48W 70.7' do

3" W. Pine N44W 60.5' do

The 1959 witness:

30" W. Pine N59E 15.5' to face.

Bearings are magnetic. Distances are to notch in lower blaze.



Signed by

Stephan J. Szyszkoski

Surveyor's Michigan License No.

33986

Date

3/30/99

For the Michigan Department of Natural Resources - Forest Management Division