

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>41N</u> R <u>29W</u>	<u>69</u>
	T <u>41N</u> R <u>29W</u>	<u>610</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling In Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sep 10 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(69) Corner common to Sections 21-22-27-28. Corner recorded in 1956 by Billy D. Buckler, RLS: "One Y. Birch stump in place (probable B.T.). Distance checks North, East and South to rock ledges and West to lake. Corner placed and witnessed August 31, 1955. Corner monument: 1" pipe with 4" brass cap. Witnesses: 15" Yellow Birch N19W 19 links, 9" Soft Maple S36E 14 links."
(610) Quarter corner common to Sections 27-28. Corner recorded in 1956 by Billy D. Buckler, RLS: "Corner found by Forestry Division Survey Crew while working in this vicinity. One W. Pine and one Y. Pine B.T. in fair condition, (Y. Pine down). This W. Pine B.T. marked by John Burt, September 28, 1849. Has date noted on tree. Corner placed and witnessed August 31, 1955. Corner monument: 1" pipe with 4" brass cap. Witnesses: 12" Hemlock S62W 66 links, 12" Cedar N2E 55 links."


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(69) Recovered the 1955 monument as described, a 1" iron pipe capped with a 4" dia. brass Michigan Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1955 witnesses, both in good condition. Left the monument in place and marked new witnesses as described below. Corner recovered and re-witnessed by B.Wheeler and D.Lampela, Baraga District Office.
(610) Recovered the 1955 monument as described, a 1" ID iron pipe capped with a 4" dia. brass Michigan Dept. of Conservation tablet, in good condition, set in a mound of rock perched on the exposed bedrock, and at record bearing and distance from the 1955 witnesses, both recovered in good condition. Recovered the rotting remains of the original B.T.s, Y. Pine 16 N58W 50, and W. Pine 18 S64E 25, at record bearing and distance. Left the monument in place and marked two new witnesses as described below. Corner recovered and re-witnessed by B.Wheeler and D.Lampela, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(69) Fd. 1" pipe with 4" brass cap.
Blazed and scribed the following:
11" Maple N82E 13.9' "S22 NBT"
8" Cedar S88W 21.4' "S28 NBT"
The 1955 witnesses:
20" Y. Birch N15W 19 links. Old blaze
11" Maple S31E 14 links. do
Bearings are magnetic. Distances are to notch in lower blaze.

(610) Fd. 1" pipe with 4" brass cap.
Blazed and scribed the following:
10" Maple S82E 15.2' "1/4S NBT"
9" Sugar N31W 39.8' do
Distances are to notch in lower blaze.
The 1955 witnesses:
15" Hemlock S63W 66 links
14" Cedar N06E 55 links
Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 3/30/97

For the Michigan Department of Natural Resources - Forest Management Division