

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T41N R 29W 611  
T41N R 29W 113

2. Property Controlling  
in Section

S T R  
S T R

3. Miscellaneous  
Property in Sec.

S T R  
S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

113 Sep 10 1998

611 Sep 16 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	19	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(611) Corner common to Sections 27-28-33-34. Corner recorded in 1956 by Billy D. Buckler, RLS: "Corner set by proportionate measure south and west to lake shore and north to swamp edge. Two old turnouts (probable B.T.s). There is an old line blazed north and south from this point. Corner placed and witnessed August 31, 1955. Corner monument: 1" pipe with 4" brass cap. Witnesses: 14" Red Pine S57E 17 links, 14" White Pine N47W 21 links."

(113) Standard Corner common to Sections 34-35, T41N-R29W. This corner was reestablished in 1954 by Billy D. Buckler: "Corner was established by proportionate measurement by Forestry Division survey crew while making a partial resurvey of this area. Corner was placed and witnessed July 27, 1954. Description of corner monument: 1" pipe with 4" brass cap. No witness trees available. Corner lies on west side of large rock".

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(611) Recovered the 1955 monument as described, a 1" ID iron pipe capped with a 4" dia. brass Michigan Dept. of Conservation tablet, in good condition, set in a rock mound 2 ft. in diameter and 1.5 ft. tall, projecting 1.5' above the mound, and at record bearing and distance from the 1955 witnesses. The R. Pine is in good condition. The W. pine is a standing 8 ft. high stub. Left the monument in place and marked three new witnesses as described below. Corner recovered and re-witnessed by B.Wheeler and D.Lampela, Baraga District Office.

(113) Recovered the 1954 monument as described, a 1" ID iron pipe capped with a 4" dia. brass Michigan Dept. of Conservation tablet, in good condition, set in a mound of rock. Mean true bearings and distances West and East to adjacent corners H13 and K13, established in 1954 of N89 deg. 59' 50"W 39.877 ch. and S89 deg. 58' 29"E 79.830 ch. suggest that the corner is in the 1954 position. I accept the monument as a careful and faithful reestablishment of the position of the original corner. Left the monument in place and marked new witnesses as described below. Corner recovered and re-witnessed by B.Wheeler and D.Lampela, Baraga District Office.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(611) Fd. 1" pipe with 4" brass cap.  
Blazed and scribed the following:  
8" R. Pine N17E 7.4' "S27 NBT"  
10" R. Pine N60E 6.8' "S27 NBT"  
11" R. Pine S60W 22.4'(slope) "S33 NBT"  
The 1955 witness 14" R. Pine S51E 17 links with old blaze, scribing visible.  
Bearings are magnetic. Distances are to notch in lower blaze.

(113) Found 1" pipe with 4" brass cap.  
Blazed and scribed the following:  
7" Spruce N08E 22.4' "S35 NBT"  
6" Spruce N81E 28.5'(slope) do  
6" Balsam S32E 13.3'(slope) "S5 NBT"  
9" Maple S77W 65.2'(slope) do  
Distances are to notch in lower blaze.  
Bearings are magnetic.



Signed by

*Stephan J. Szyszkoski*

Surveyor's Michigan License No.

33986

Date

3/30/99

For the Michigan Department of Natural Resources - Forest Management Division