

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey	T41N R 29W	M9
	T_____ R_____	_____
	T_____ R_____	_____
	T_____ R_____	_____
2. Property Controlling in Section	S 25 T41N R 29W	5
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

5 Nov 29 1998

M9 Sep 10 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
(M9) Corner common to Sections 24-25 T41N-R29W and 19-30 T41N-R28W. Remonumented by Billy D. Buckler, RLS in 1959: "This corner was replaced from two W. Pine B.T.'s. Both stumps are badly burned and rotted. Distance north to stream checks good. Corner was placed and witnessed September 21, 1959 with Frank J. Bray. Description of corner monument: 1" pipe with 4" brass cap. Witnesses to corner: 24" W. Pine snag N40E 38 links, 6" Aspen S52E 26 links, 8" W. Birch N38W 38 links."
(5-Sec. 25) North 1/16 corner Section 25. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M9) Recovered the 1959 monument as described, a 1" ID iron pipe capped with a 4" dia. brass Michigan Dept. of Conservation tablet, in good condition, at record bearing and distance from the ground level remains of the original W. Pine bearing trees: S86E 25.1' and N35W 19.8'. Also at record bearing and distance are the 1959 witnesses: the W. Pine is down on the ground (scribing visible), the Aspen is a rotted stump, and the W. Birch is in good condition with overgrown blaze. I accept the monument as a careful and faithful perpetuation of the position of the original corner. Left the monument in place and made measurements to 4 existing bearing trees marked by person(s) unknown after 1959. Corner recovered and re-witnessed by D.Lampela and B.Wheeler, Baraga District Office.
(5-Sec. 25) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Quarter corner 1314.74' north and Center of Section 1314.74' south. At the position for the corner I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by B.Wheeler and D.Lampela, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M9) Found 1" pipe with 4" brass cap.	(5) Set 1" pipe with 4" MDNR cap.
Found the following trees marked with BH blaze:	Blazed and scribed the following:
11" W. Spruce N11W 25.1' to meas. nail	10" Maple N54E 21.7' "1/16S BT"
9" Aspen N53E 13.1' do	14" W. Pine S05E 78.2' do
10" Aspen S18W 13.7' do	9" double Maple S03W 25.1' do
14" R. Maple S65W 30.4' do	18" R. Pine N32W 71.6' do
Bearings are magnetic. Placed a squared spruce post adjacent.	Placed a squared cedar post adjacent.
	Bearings are magnetic. Distances are to notch in lower blaze.



Signed by

Stephan J. Szyszkoski

Date

3/30/99

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division