

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T41N R 29W M11

T41N R 29W I10

T R

T R

2. Property Controlling
In Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I10 Sep 09 1998

M11 Sep 10 1998

I, Stephan J. Szyzkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(M11) Corner common to Sections 25-36 T41N-R29W and Sections 30-31 T41N-R28W. Corner re-monumented in the original position by Billy D. Buckler in 1954: "This corner was found by Forestry division survey crew, while making a partial resurvey of this area. 3 original B.T.'s still in place, in good condition. Corner was placed and witnessed July 26, 1954. Description of corner monument: 1" pipe with 4" brass cap. Witnesses to corner 10" Cedar S60E 29 links, 12" Cedar S85W 30 links."

(I10) Quarter corner common to Sections 26-27. Established in 1849 by John Burt: "North between Sections 26 & 27...40.00 Set Cedar Qr. Sec. post. W. Pine 36 S80W 5, Hemlock 18 N67E 24."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M11) Recovered the 1954 monument as described, a 1" ID iron pipe capped with a 4" dia. brass Michigan Dept. of Conservation tablet, in good condition, and at record bearing and distance from the two 1954 Cedar NBT's, found in good condition. Someone has placed measuring nails in the sides of the trees and also in two other nearby Cedars. The original Cedar BT's were found at record bearing and distance, burned and very rotten, with no visible marks. I accept the monument as a careful and faithful perpetuation of the position of the original corner. Left the monument in place and made measurements to the existing NBTs. Corner recovered and re-witnessed by D.Laapala and B. Wheeler, Baraga District Office.

(I10) Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of mean true bearing between Section corners 2630.74' north and south. At the position for the corner I placed a 1"IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Laapala and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M11) Found 1" pipe with 4" brass cap.

Found nails in the sides of the following trees:

18" Cedar S56E 19.5' with old blazes

14" Cedar West 20.1 do

12" Cedar N39W 19.5'

13" Cedar N71E 41.2'

Bearings are magnetic. Distances are to the nails.

(I10) Set 1" pipe with 4" MDNR cap.

Blazed and scribed the following:

4" Spruce S24W 16.15' 1/4S NBT

5" Spruce S40W 34.4' do

5" Spruce N85W 26.9' do

12" twin W.Pine S27E 88.0' do

Placed a squared cedar post adjacent.

Bearings are magnetic. Distances are to notch in lower blaze.



Signed by

Stephan J. Szyzkoski

Date

3/30/99

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division