

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located in:

Corner Code #

1. Public Land Survey

T41N R 29W M12

T41N R 29W K13

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Sep 10 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
(M12) Quarter corner common to Section 36 T41N-R29W and Section 31 T41N-R28W. Corner re-monumented in the original position by Billy D. Buckler, RLS, in 1954: "This corner was found by Forestry Division survey crew, while making a partial resurvey of this area. One original B.T. still in place, in good condition. Corner was placed and witnessed July 26, 1954. Description of corner monument: 1" pipe with 4" brass cap. Witnesses to corner: 14" Cedar N76W 48 links, 16" W. Pine N04E 64 links."  
(K13) Standard corner common to Sections 35-36 T41N-R29W. Corner re-monumented in the original position in 1951 by Dean C. DeLaMater, RLS: "This corner was pointed out to be by N. S. Paterson, District Forester, of Iron Mountain. One original B.T. in place, in good condition. Corner was placed and witnessed October 11, 1951. Description of corner monument: 1" pipe with 4" brass cap. Witnesses to corner: 10" Cedar N60W 28 links, 8" Red Oak S49W 46 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M12) Recovered the 1954 monument as described, a 1" ID iron pipe capped with a broken 4" dia. brass Michigan Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1954 witnesses, both in good condition. The original Cedar BT S30W was found a rotting stub with blaze and some scribing still visible, at record bearing and distance. I accept the monument as a careful and faithful perpetuation of the position of the original corner. Left the monument in place and marked two new accessories as described below. Corner recovered and re-witnessed by B.Wheeler and D.Lampela, Baraga District Office.

(K13) Recovered the 1951 monument as described, a 1" ID iron pipe capped with a 4" brass Michigan Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1951 witnesses, both in good condition with blazes overgrown. I accept the monument as a careful and faithful perpetuation of the position of the original corner. Left the monument in place and marked two new NBT's as described below. Corner recovered and re-witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M12) Found 1" pipe with brass cap. Blazed and scribed the following:  
11" Cedar S45E 46.6' "1/4S NBT"  
15" Cedar S09W 43.7' do  
The 1954 witnesses:  
18" Cedar N70W 31.4' overgrown blazes  
18" R. Pine N08E 42.7' do  
Bearings are magnetic. Distances are to notch in lower blaze.

(K13) Found 1" pipe with 4" brass cap. Blazed and scribed the following:  
7" Maple N66E 16.9' "S36 NBT"  
8" Double Maple N70W 43.4' "S35 NBT"  
The 1951 witnesses:  
11" Cedar N56W 18.5' overgrown blazes  
15" Red Oak S51W 30.4' do  
Bearings are magnetic. Distances are to notch in lower blaze. Placed a squared cedar post adjacent.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 3/30/99

For the Michigan Department of Natural Resources - Forest Management Division