

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T41N R 29W J9

T R

T R

T R

2. Property Controlling  
In Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Jun 01 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9									●				
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(J9) Quarter corner common to Sections 23-26. Established in 1849 by John Burt: West Corner between 23 & 26 "39.40 Brook 5 L C. NE, 40.00 Set Cedar Cr. Section post. Y. Birch 10 N45W 52, Cedar 10 S30E 27". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J9) Original post was not recovered. Found a squared wooden post, placed by persons unknown at record bearing and distance from what appears to be the remains of the original Cedar 87, now an 18" stump found with a section of the NW face removed by a power saw. The part removed would correspond to the scribed blaze made in the original survey. The Y. Birch 87 was not recovered and its remains were probably removed by road construction. An original corner bears S89 deg 41'41"E (true) 40.1318 ch. and a probable original corner bears N89 deg. 28'19"W 39.8779 ch. The corner is at the west edge of the brook noted in the record. However, this call was probably transcribed from the random line notes and consequently should not be given excessive weight. I accept the wooden post as the best available evidence of the position of the original corner and, in its place, drive a 1" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J9) Set a 1" iron pipe with 4" MDNR cap. Blazed and scribed the following:  
 20" Cedar N76E 12.8' "1/4S NBT"  
 10" Cedar S46E 22.1' do  
 12" Cedar S30W 16.3' do  
 9" Y. Birch N81W 20.4' do  
 Bearings are magnetic. Distances are to notch in the lower blaze.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 3/30/99

For the Michigan Department of Natural Resources - Forest Management Division