

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey	T41N R 29W	III
	T R	
	T R	
	T R	
2. Property Controlling in Section	S25 T41N R 29W	9
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

9 Oct 28 1998

III Oct 17 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(III) Corner common to Sections 26-27-34-35. Established in 1849 by John Burt: "North between 34 & 35...80.00 Set Cedar post corner of sections 26,27,34 & 35. Henlock 18 N24W 42, Henlock 12 S50E 10."

(9-Sec. 25) East 1/16 corner Section 25. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(III) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by double proportionate measurement to the original record between monumented corners 79.7193 ch. northerly, 79.7791 ch. easterly, 79.7165 ch. southerly, and 79.7790 ch. westerly. At the position for the corner I placed a 1"IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped, set firm in a mound of rock and portland cement concrete. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

(9-Sec. 25) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Center of Section 1328.58' west and Quarter corner 1328.58' east. At the position for the corner, which falls on a rock outcrop, I chisel an "x", and erect above it a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped, made firm in a mound of rock 5' long by 3' wide by 2.5' high. Corner placed and witnessed by B.Wheeler and D.Lampela, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(III) Set 1" pipe with 4" MDNR cap.

Blazed and scribed the following:

4" Spruce N33E 81.55' "S26 NBT"

5" Aspen S84E 31.05' "S35 NBT"

3" Aspen S34E 43.3' "S35 NBT"

2" Aspen S80W 15.3' "X X"

Placed a squared cedar post S8E 2.6'.

Bearings are magnetic. Distances are measured on the slope and are to a notch in the lower blaze.

(9) Chiselled "x" and 1" pipe with 4"

MDNR cap. Blazed and scribed the

following bearing trees:

8" triple W.Birch S73W 68.65"1/16S BT"

10" Balsam S69E 21.1' do

5" Balsam N53E 54.7' do

5" twin Maple N20E 45.15' do

Cedar post adjacent in the rock mound.

Bearings are magnetic. Distances are to notch in lower blaze.



Signed by

Stephan J. Szyszkoski

Date

3/30/99

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division