

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson	Located In:	Corner Code #
(County)		
1. Public Land Survey	T41N R 29W	K10
	T41N R 29W	K11
	T_____ R_____	_____
	T_____ R_____	_____
2. Property Controlling in Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

K11 Sep 14 1998

K10 Sep 09 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(K10) Quarter corner common to Sections 25-26. Established in 1849 by John Burt: "North between Sections 25 & 26...40.00 Set Hemlock Br. Sect. post. Hemlock 18 N50E 25, Hemlock 10 S48W 18."

(K11) Corner common to Sections 25-26-35-36. Established in 1849 by John Burt: "North between Sections 35 & 36...80.00 Set Hemlock post Cor. of Sections 25, 26, 35 & 36. Y. Birch 14 N50W 35, Cedar 10 S8E 19."

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(K10) The Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of mean true bearing between Section corners 2620.10' north and south. At the position for the corner I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped, and set firm in a mound of rock. Corner placed and witnessed by B.Wheeler and D.Lampela, Baraga District Office.

(K11) Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by double proportionate measurement to the original record between monumented original corners 79.3967 ch. north (80.0 R), 39.6979 ch. south (40.0 R), 40.0504 ch. west (39.95 R), and 80.1240 ch. east (79.94 R). At the position for the corner I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(K10) Set 1" pipe with 4" MDNR cap.  
Blazed and scribed the following:  
8" R. Pine N24N 27.25' 1/4S NBT"  
5" Maple N55W 47.5' do  
5" Spruce N89E 66.0' do  
2" Spruce S76W 14.1' do  
Placed a squared cedar post adjacent.  
Bearings are magnetic. Distances to notch in lower blaze.

(K11) Set 1" pipe with 4" MDNR cap.  
Blazed and scribed the following:  
7" Spruce N86W 4.3' "S26 NBT"  
9" Spruce South 14.6' "S35 NBT"  
12" Spruce N88E 37.0' "S25 NBT"  
6" Maple N71W 31.5' "S26 NBT"  
Placed a squared cedar post adjacent.  
Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 3/30/99

For the Michigan Department of Natural Resources - Forest Management Division