

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T41N R 29W 612

T R

T R

T R

2. Property Controlling
in Section

S26 T41N R 29W 5

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

5 Oct 20 1998

612 Sep 03 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(612) Quarter corner common to Sections 33-34. Reestablished in 1961 by Billy D. Buckler: "This corner was reestablished on line between two Section Corners and at 40.00 chains from South Section Corner. The North 1/2 mile is short because of error in measuring in the original survey. Note: Pipe is 2 links South of Actual Corner. Corner monument: X mark chiseled on rock ledge. 1" pipe with 4" brass cap 2 links south of corner. Witnesses: 8" Soft Maple N28E 63.5 links, 7" Hard Maple S40E 82 links."

(5-Sec. 26) North 1/16 corner Section 26. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(612) Recovered the 1961 corner as described, a chiseled "+" on exposed rock face and the 1" iron pipe capped with a 4" brass Michigan Dept. of Conservation tablet, both in good condition, and the "+" being at record bearing and distance from the 1961 witnesses, both recovered in good condition, with the 1961 blazes overgrown. My measurements show the "+" to be 6.6' West and 3.5' South of the record 1961 position. I accept same as a careful and faithful reestablishment of the position of the original corner. Left the monuments in place and marked two new accessories as described below. Corner recovered and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

(5-Sec. 26) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Quarter corner 1310.06' north and Center of Section 1310.06' south. At the position for the corner I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by B.Wheeler and D.Lampela, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(612) Fd. chiseled "+" on rock face.

Blazed and scribed the following:

4" W. Pine S46W 37.3' 1/4S NBT

12" W. Pine N16W 37.0' do

the 1961 witnesses:

12" Maple N33E 41.9' overgrown blazes

10" Sugar S37E 54.1' do

1" pipe with 4" brass cap 1.2'

southerly. Bearings are magnetic.

Distances to notch in lower blaze.

(5) Set 1" pipe with 4" MDNR cap.

Blazed and scribed the following:

15" R. Pine S06W 16.05' 1/16S BT

9" R. Pine S66E 27.8' do

15" R. Pine N15E 38.5' do

8" W. Birch N48W 33.35' do

Placed a squared cedar post adjacent.

Bearings are magnetic. Distances are to

notch in lower blaze.



Signed by

Stephan J. Szyszkoski

Date

3/30/99

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

REVISED OCT., 1985