

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T41N R 29W	K12
	T41N R 29W	L11
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

L11 Sep 10 1998  
K12 Jun 01 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	8		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(K12) Quarter corner common to Sections 35-36. Established in 1849 by John Burt: "North between Sections 35-36...40.00 Set Y. Birch Cr. Sect. post. Hemlock 14 N28E 10, do 14 S61W 45."

(L11) Quarter corner common to Sections 25-36. Established in 1849 by John Burt: "West corrected [between Sects. 25 & 36]...39.97 Set Cedar Cr. Section post. W. Pine 8 N41W 15, Aspen 8 S28E 27."

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(K12) Re-monumented the corner in the original position as determined by the remains of the original Y. Birch post, recovered as a small circle of rotted wood approx. 3" in dia. with accompanying remains of Y. Birch bark. The original Hemlock BT remains, now very rotted stumps with no markings visible, were both found at record bearing and distance. An original corner bears S12'E (true) 39.7936 chains. At the position of the remains of the post, I place a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

(L11) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of mean true bearing between Section corners 2644.09' east and west. At the position for the corner I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped, set in a crack in the bedrock and made firm with a mound of rock 2.5' in dia. and 1' high. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(K12) Set 1" pipe with 4" MDNR cap.  
Blazed and scribed the following:  
8" Sugar N53E 31.8' "1/4S NBT"  
8" Sugar S41E 6.8' do  
5" Sugar S85W 15.0' do  
6" twin Sugars N10W 19.0' do  
Placed a squared balsam post adjacent.  
Bearings are magnetic. Distances are to notch in lower blaze.

(L11) Set 1" pipe with 4" MDNR cap.  
Blazed and scribed the following:  
5" Spruce N67E 18.0' "1/4S NBT"  
9" Spruce S20E 44.3' do  
8" dbl Maple N46W 31.2' do  
4" twin Maple S70E 13.1' (slope) do  
Placed a squared maple post adjacent.  
Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 3/30/99

For the Michigan Department of Natural Resources - Forest Management Division