

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Dickinson</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T41N R 29W	G13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sep 03 1998

I, Stephen J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(G13) Standard corner common to Sections 33-34 T41N-R29W and Sections 6 T40N-R29W. Corner perpetuated in 1955 by Billy D. Buckler, RL5: "One Cedar stump (possible B.T.) Distance E. & W. checks to good corners. Distance North to lake checks. Corner set on edge of lake at high water mark. Corner placed and witnessed July 20, 1955. Corner monument: 1" pipe with 4" brass cap. Witnesses to corner: 32" White Pine stub N58W 74 links, 8" White Birch S77W 24 links." LCRC dated January, 1962 by Billy D. Buckler says that "+" chisled on rock at G12 is 40.00 ch. north of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G13) Recovered the 1955 monument, a 1" iron pipe capped with a 4" dia. brass Michigan Dept. of Conservation tablet, found encased in a monument of concrete, 4" dia., formed by a concrete filled 4" ID concrete pipe of unknown length, with 6" bell, in good condition, projecting approximately 1 foot. No trace remains of the B.T. cedar noted in the 1955 record or of the two 1955 MBT's. Distance east to a Michigan Dept. of Conservation monument is 2651.35' and north to a "+" chiseled at G12 is 2636.48'. I accept the position of the monument as being the 1955 position and the best available evidence of the position of the original corner. Left the monument in place and marked new witnesses as described below. Recovered and re-witnessed by D.Laapela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G13) Found 1" pipe with 4" brass cap set in concrete monument. Blazed and scribed the following:

4" Maple N14E 41.7' "S34 NBT"
6" Sugar N40W 24.3' "S33 NBT"
13" double Sugar S44W 56.6' (slope) to nail and DNR washer.

S69W 96.5' to NE cor. of most N'y camp bldg. on E.shore lake. Placed cedar post adjacent. Brgs. are magnetic. Shoreline is 15' East.

Signed by Stephen J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 3/30/99



For the Michigan Department of Natural Resources - Forest Management Division