RECORDED

1999 NOV 30 PM 3:23

REGISTER OF DEEDS
DICKINSON COUNTY

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

DICKINSON (County)
SAGOLA TOWNSHIP
BREITUNG TOWNSHIP

Located In: Corner

1. Public Land Survey T 41 N R 30 W B-7
   T 41 N R 30 W C-10
   T____ R____
   T____ R____
2. Property Controlling S____ T____ R____
   in Section S____ T____ R____
3. Miscellaneous S____ T____ R____
   Property in Sec. S____ T____ R____

SURVEY & REMONUMENTATION
MAR 24 2000
SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____



I, JAMES H. MOORE, in a field survey on AUGUST 18, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-7 ¼ CORNER COMMON TO SECTIONS 18 AND 19.
POST BY JOHN BURT, D.S. 1849
ASPEN 12" EAST 9.59 CHAINS
ASPEN 12" WEST 10.12 CHAINS

C-10 ¼ CORNER COMMON TO SECTIONS 29 AND 30.
POST BY JOHN BURT, D.S. 1849
ASPEN 9" N 85° W 5 LINKS
ASPEN 9" S 26° E 24 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-7 FOUND 1-1/2" PIPE AT GROUND LEVEL WITH A 3" X 3" SQUARE POST. PER ROBERT SPEAR REMONUMENTATION REPORT DATED 12-7-98.

C-10 FOUND 5/8" REBAR AND CAP APPOXIMATELY 0.10' BELOW GRAVEL ROAD, RLS 15408. PER ROBERT SPEAR REMONUMENTATION REPORT DATED 12-7-98.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7 SET DICKINSON COUNTY 4" ALUMINUM CAP INSIDE EXISTING MONUMENT.
NEW WITNESSES.

BLACK SPRUCE 7"	S 05° W	(M.B.)	20.25'	NAIL/TAG
CEDAR 12"	N 44° W	(M.B.)	8.77'	NAIL/TAG
BALSAM 6"	N 01° E	(M.B.)	18.25'	NAIL/TAG
BLACK SPRUCE 6"	S 40° E	(M.B.)	16.15'	NAIL/TAG
CARSONITE MARKER	N 76° E		1.00'	

C-10 SET DICKINSON COUNTY MONUMENT WITH 4" ALUMINUM CAP.
NEW WITNESSES.

EXISTING B.T. 16" WHITE BIRCH	S 66° W	(M.B.)	64.09'	NAIL/TAG
MAPLE 8"	N 14° E	(M.B.)	52.76'	NAIL/TAG
SPRUCE 4"	N 65° E	(M.B.)	40.40'	NAIL/TAG
BALSAM 5"	N 76° W	(M.B.)	56.91'	NAIL/TAG
CARSONITE MARKER	WEST		20.50'	
REFERENCE MONUMENT	WEST		20.00'	

Signed by James H. Moore Date 11-8-99

Surveyor's Michigan License No. P.S. 28423

STATE OF MICHIGAN
JAMES H. MOORE
LAND SURVEYOR
No. 28423
LICENSED LAND SURVEYOR

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14,1975
REVISED JAN., 1983
REVISED OCT., 1995

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-23-99

COUNTY REPRESENTATIVE

LIBER 3 PAGE 15