

SURVEY &
REMONUMENTATION

RECORDED

MAY 07 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1996 DEC 10 AM 9:59

For corners in Dickinson **COMMISSION**
(County)

Located In:

Corner Code #

Sagola Township

REGISTER OF DEEDS
DICKINSON COUNTY
IRON MOUNTAIN MI 49801

- | | | | | | |
|--------------------------------------|---|-----|---|-----|-------|
| 1. Public Land Survey | T | 41N | R | 30W | C-7 ✓ |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Section | S | | T | R | |
| | S | | T | R | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, James H. Moore, in a field survey on 7/23 thru 8/6, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-7 1849 John Burt, D.S. North, 80.00 ch. set Cedar post.
Cedar 10" S 50° W, 18 lks Sugar 16" N 64° E, 37 lks

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-9-96
RAP
COUNTY REPRESENTATIVE

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7			●										
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7 John and Rudy Mashak indicated the pipe was in the centerline of the woods road and showed me, to the best of their recollection, the corner position where I found a bent pipe laying along side woods road in small berm. I also found a distance from the Northwest corner of Section 17 to the Southwest corner of Sectin 17 of 5155.40' in old Dickinson Co. Road Commission records. I re-established corner in the centerline of the woods road and at record distance from the Northwest corner of Section 17, which agrees with location indicated by the Mashak brothers.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7 Set Aluminum Dickinson County Monument in centerline woods road approximately 4" below grade. Referenced as follows:
Sugar 7" N 10° W, 32.05' White Birch 4" N 66° E, 17.43'
White Birch 5" S 86° E, 9.38' Maple 10" N 82° W, 26.10'
Carsonite Witness Post South 6.0'

Signed by James H. Moore
Surveyor's Michigan License No. _____

Date 9/10/96