

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1998 DEC 14 PM 12: 25

For corners in

Dickinson

(County)

Breitung

Located In:

Corner Code #

1. Public Land Survey

T 41N R 30W

C-9

T ___ R ___

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

REGISTER OF DEEDS
 DICKINSON COUNTY
 201 N. W. 1st St. Breitung, MI 49801

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert F. Perkins, in a field survey on Oct. 23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:


C-9 Corner Common to Sections 19-20-29-30
 Post by John Burt, D.S. 1849
 Original Bearing Trees
 Aspen 6" S28°W 25 Lk.
 Tamarack 16" N15°E 21 Lk.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9 No Evidence of Original Corner or its Accessories Found.
 Found 3" Iron Pipe at Fence Corner placed by the undersigned
 10-27-1972 as described in L.C.R.C. Certificate No. 45.
 1972 Bearing Trees: B. Ash 5" N42°E 26.55' (Found)
 Maple 5" S63°E 47.23'
 Dbl. Birch 14" N82°W 28.77' (Found)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9 Accepted 3" Iron Pipe described in "B" above as Best Available Evidence of Corner Location. Placed 2 1/2"
 Stamped D.C. Remon. Corner inside of Existing 3" Iron Pipe.
 Witnesses: Fir 4" N84°E(M.B.) 10.05' (Nail/Tag)
 B. Ash 7" N42°E 26.55' Ex. B.T.
 W. Pine 4" S03°E(M.B.) 50.50' Nail/Tag
 Dbl. W. Birch 16" N82°W 29.05'
 Placed Carsonite Marker N05°W 0.70'



Signed by Robert F. Perkins

Date Nov. 20, 1998

Surveyor's Michigan License No. 12027

RECEIVED BY THE DICKINSON COUNTY
 SURVEY PEER GROUP AS THE OFFICIAL
 CORNER UNDER MICHIGAN PUBLIC ACT
 345 OF 1990 AT A MEETING HELD ON
12-7-98

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995

R.F. Perkins
 COUNTY REPRESENTATIVE

Liber 2 Page 410