

Commo To T41N R30W
DIB ✓

RECORDED

1998 JUN 12 AM 8:58

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson
(County)
Breitung Township

Located in:

Corner Code #

1. Public Land Survey

T 40N R 30W

D-1

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

REGISTER OF DEEDS
DICKINSON COUNTY
IRON MOUNTAIN, MI 49901

SURVEY &
REMONUMENTATION

NOV 15 1999

SECTION

Register of Deeds Stamp & File Number

I, Ewart C. Muller, in a field survey on May 20, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Wm Austin Burt ran 4th Correction Line in 1846
J.H. Mullet Subdivided Township in 1849

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-1 Corner not set in Original Survey. No Subsequent corner found. Corner lies on North edge of a cleared Power Company Tower right-of-way

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 Set 1/4 corner Midway on arc 2635.05 feet East of Dickinson County Monumented Closing Corner of Sections 5 & 6 and 2635.05 feet West of DNR Monumented Closing Corner of Sections 4 & 5

ACCEPTED BY THE DICKINSON COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT
345 OF 1990 AT A MEETING HELD ON

6-4-98
RSP

COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


D-1 Set Aluminum Rod with 3/4-inch Dickinson County Aluminum Cap Stamped N 1/4 S5, T40N,R30W and T41N,R30W above

Witnesses: Triple Red Maple 10, N4W 16.60; Red Maple 9 N76E 27.35; Double Red Oak 10 S10E 99.25;
Red Oak 6 S40E 127.22.

All Bearings Magnetic. Measurements to a nail in sides of trees.

Signed by Ewart C Muller

Surveyor's Michigan License No. 15408



Date June 3, 1998

Lianna D. ...