

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1999 NOV 30 PM 3:29

For corners in

DICKINSON Located In: _____ Corner Code # _____
 (County)
BREITUNG TOWNSHIP

1. Public Land Survey T 41 N R 30 W D-9
 T 41 N R 30 W E-9
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

SURVEY &
 REMONUMENTATION
 MAR 24 2000

REGISTRY OF DEEDS
 REGISTERED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____ SECTION _____

5. Private Claims _____

I, JAMES H. MOORE, in a field survey on AUGUST 18, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-9 ¼ CORNER COMMON TO SECTIONS 20 - 29
 CEDAR POST BY JOHN BURT, D.S. 1849
 WHITE BIRCH 6" S 51° W 5 LINKS
 TAMARACK 5" NORTH 14 LINKS

E-9 CORNER COMMON TO SECTIONS 20 - 21 - 28 - 29
 SUGAR POST BY JOHN BURT, D.S. 1849
 WHITE PINE 22" N 78° E 36 LINKS
 ASPEN 9" S 78° W 20 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9 FOUND 1 ½" PIPE. PER ROBERT SPEAR
 REMONUMENTATION REPORT
 DATED 12-7-98.

E-9 FOUND 1 ½" PIPE. FOUND EXISTING B.T. PER
 ROBERT SPEAR REMONUMENTATION REPORT
 DATED 12-7-98.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


D-9 SET DICKINSON COUNTY MONUMENT WITH 4"
 ALUMINUM CAP. NEW WITNESSES.

E-9 SET DICKINSON COUNTY MONUMENT WITH 4" ALUMINUM
 CAP. NEW WITNESSES.

EXISTING B.T. 6" CEDAR S 58° E (M.B.) 24.12' NAIL/TAG
 7" CEDAR N 68° E (M.B.) 24.92' NAIL/TAG
 9" CEDAR N 36° W (M.B.) 22.75' NAIL/TAG
 9" CEDAR S 75° W (M.B.) 22.44' NAIL/TAG
 CARSONITE MARKER NORTH (M.B.) 0.40'

EXISTING 15" OAK N 77° E (M.B.) 11.00' NAIL/TAG
 4" BALSAM N 24° W (M.B.) 21.10' NAIL/TAG
 4" MAPLE N 87° W (M.B.) 22.90' NAIL/TAG
 5" MAPLE S 41° E (M.B.) 46.56' NAIL/TAG
 CARSONITE MARKER NORTH (M.B.) 1.00'

Signed by _____ Date 11-8-99
 Surveyor's Michigan License JAMES H. MOORE 28423



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995

ACCEPTED BY THE DICKINSON COUNTY
 SURVEY PEER GROUP AS THE OFFICIAL
 CORNER UNDER MICHIGAN PUBLIC ACT
 345 OF 1990 AT A MEETING HELD ON
11-23-99
ROBERT SPEAR
 COUNTY REPRESENTATIVE

Liber 3 PAGE 14