

RECORDED

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 1998 DEC 14 PM 12: 26

For corners in

Dickinson

(County)

Breitung Twp.

1. Public Land Survey

Located In:

Corner Code #

T 41NR 30W

G-8

G-13

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

SURVEY & RECONSTRUCTION

1999

REGISTER OF DEEDS  
DICKINSON COUNTY  
IRON MOUNTAIN, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

SECTION

I, Robert F. Perkins, in a field survey on Sept. 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-8 1/4 Corner Common to Sections 21/22  
Post by John Burt, D.S. 1849  
Original Bearing Trees  
Cedar 14" N40°E(M.B.) 25 Lk.  
W. Birch 10" S72°W(M.B.) 15 Lk.

G-13 Southeast Corner Section 33  
Post by W. A. Burt, D.S. 1846  
Original Bearing Trees  
Hemlock 8" S31°E 10 Lk.  
Spruce 6" S48°W 20 Lk.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8 No Evidence of Original Corner or its Accessories Found.  
Found 1" Iron Pipe Noted on Certificate #364 signed by James H. Moore, RLS dated 3-18-84.

G-13 No Evidence of Original Corner or its Accessories Found.  
Found 2 1/2" Iron Pipe and Bearing Trees referred to in M.D.O.T. Corner Report signed by J.P. Smallwood RLS dated 4-16-64. Report #821.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8 Replaced 1" Iron Pipe referred to in "B" above with 2 1/2" Stamped D.C. Remon Corner.  
New Witnesses:  
W. Birch 10" N70°E(M.B.) 15.38' Nail/Tag  
Cherry 4" N04°E(M.B.) 12.79' Nail/Tag  
Maple 2" S68°W(M.B.) 10.18' Nail/Tag  
Maple 4" S02°E(M.B.) 25.11' Nail/Tag  
Placed Carsonite Marker 1.0' South

G-13 Placed 2 1/2" Stamped D.C. Remon. Corner inside of Existing 2 1/2" Iron Pipe referred to in "B" above.  
New Witnesses:  
Maple 6" N45°W(M.B.) 41.15' Nail/Tag  
Maple 10" N5°E(M.B.) 25.60' Nail/Tag  
Maple 8" N30°E(M.B.) 25.70' Nail/Tag  
W. Pine 3" N34°W(M.B.) 47.55' Centerline  
Placed Carsonite Marker 0.8' North.

Signed by Robert F. Perkins Date Oct. 28, 1998

Surveyor's Michigan License No. 12027

RECORDED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 12-7-98

