

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1998 DEC 14 PM 12: 26

For corners in

Dickinson  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 41NR 30W

1-11 Breitung Twp.

T R

K-6 Sagola Twp.

T R

T R

2. Property Controlling  
in Section

S T R

SURVEY &  
REMONUMENTATION

3. Miscellaneous  
Property in Sec.

S T R

S T R

MAR 11 1999

REGISTER OF DEEDS  
DICKINSON COUNTY  
IRON MOUNTAIN MI 49801

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ SECTION \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14	●	13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11									●				
12		31		32		33		34		35		36	
13													

I, Robert F. Perkins, in a field survey on Sept. 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-11 Corner Common to Sections 26-27-34 & 35 K-6  
Post by John Burt, D.S. 1849  
Original Bearing Trees  
W. Birch 10" N38°E 36 Lk.  
Hemlock 6" S67°W 37 Lk.

¼ Corner Common to Sections 14/13  
Post by John Burt, D.S. 1849  
Original Bearing Trees  
Tamarack 12" S54°W 73 Lk.  
Tamarack 14" S52°E 110 Lk.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 No Evidence of Original Corner  
or Accessories Found.  
4-29-64 C.C. Lundgren M.D.O.T. Found  
and Witnessed 1½" Iron Pipe.  
Old Report #819  
W. Birch 12" N65°W 80.36'  
Poplar 10" N25°W 41.55'  
S.W. Leg of Tower N40°E 53.02'

K-6 No Evidence of Original Corner  
or its Accessories Found.  
Found 1" Iron Pipe with 4" D.N.R.  
Stamped Cap set by B. Buckler, RLS 1963  
20" Y. Pine S79°W 236 Lk.  
Location agrees with G.L.O. Calls  
Old Corner Report #739

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


I-11 Found 5/8" Iron Bar at above noted  
Location. Replaced Iron Bar with 2½"  
Stamped D.C. Remon. Corner.  
New Witnesses:  
N.E. Corner Garage Fd. S48°W(M.B.) 95.37'  
Spruce 12" N45°W 53.28' Nail/Tag  
Power Box (S.W. Cor.) S84°E(M.B.) 26.58'  
x Cut on S.W. Tower Leg N45°E 53.28'  
Set Carsonite Marker S82°E 27.85'

K-6 Found and Accepted Monument described  
in "B" above.  
New Witnesses:  
Y. Pine 28" S79°W(M.B.) 155.76' (1963 BT)  
Balm 9" S63°W(M.B.) 43.20' Nail/Tag  
Balm 5" N26°W(M.B.) 59.15' Nail/Tag  
Balm 4" S37°W(M.B.) 37.77' Nail/Tag  
Placed Carsonite Marker 1.0' North.

Signed by Robert F. Perkins  
Surveyor's Michigan License No. 12027

Date Oct. 28, 1998

ACCEPTED BY THE DICKINSON COUNTY  
SURVEY PEER GROUP AS THE OFFICIAL  
CORNER UNDER MICHIGAN PUBLIC  
345 OF 1990 AT A MEETING HELD  
12-2-98



Robert F. Perkins  
COUNTY REPRESENTATIVE

Liber 2

Page 423