

SURVEY & REMONUMENTATION

NOV 15 1999

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1997 OCT -9 AM 8:21

SECTION

For corners in

<u>Dickinson</u>	Located In:	Corner Code #
(County)		
Breitung Twp.		
1. Public Land Survey	T <u>41N</u> R <u>30W</u>	<u>K-10</u> ✓
	T _____ R _____	<u>L-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
DICKINSON COUNTY
RON MOUNTAIN 12 2000

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, R.F. Perkins, in a field survey on Aug. 26, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-10 West 1/4 Corner, Section 25 Post by J. Burt, D.S. 1849 Original Bearing Trees Hemlock 20" N35°W 50 Lks. Hemlock 8" S56°E 21 Lks.	L-11 South 1/4 Corner, Section 25 Post by J. Burt, D.S. 1849 Original Bearing Trees Y. Birch 14" N62°E 19 Lks. Cedar 16" S62°W 26 Lks.
---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10 No evidence of Original Corner or Accessories Found. Found 2 1/2" Solid Iron Bar with Old Bearing Trees & Old Fence running South. Iron Bar agrees with W.C. Johnson, C.E. 1937 Subdivision of Section 25 (See D.C.R.C. File A-10, No. 23B)	L-11 Found 4" B.C. D.N.R. Pipe Marker (Old Certificate #121) Found 1937 D.C.R.C. Bearing Tree Hemlock 24" (Dead) S84°E (M.B.) 51' to E Tree
---	--

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-7-97


ROTP

COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 Accepted above Iron Bar as best available evidence. Set 2 1/2" Stamped D.C. Remon. Monument at base of Iron Bar. New Witnesses P.Pole #55-774 N52°W (M.B.) 54.94' S.Maple 6" N45°E (M.B.) 45.42' S.Maple 10" S36°W (M.B.) 16.51' Y. Birch 10" S09°W (M.B.) 29.22' Placed Carsonite Marker 1.0' West.	L-11 Up-Graded above Corner with New Witnesses: S.Maple 5" N34°E (M.B.) 20.27' S.Maple 6" N13°W (M.B.) 14.62' S.Maple 5" S44°W (M.B.) 20.67' Db1. 20" S.Maple S14°E (M.B.) 13.77' Placed Carsonite Marker 2.0' South
--	---

Signed by Robert F. Perkins
ROBERT F. PERKINS
Surveyor's Michigan License No. 12027



Date PERKINS 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983