

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	DICKINSON COUNTY LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. <del>S.</del> , R. 30 <del>E.</del> W.	I6
2. PROPERTY CONTROLLING IN SECTION	15, T. 41 N. <del>S.</del> , R. 30 <del>E.</del> W.	7, 14
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. <del>S.</del> , R. _____ E. <del>W.</del>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 9, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner I6: Original monument and accessories not found.
  - Corner 7: Not set on original survey nor subsequently apparently.
  - Corner 14: Not set on original survey nor subsequently apparently.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner I6: Restored corner midway and on line between section corners 2628.90 ft. north and south.
  - Corner 7: Established midway and on line between corners 1314.45 ft. north and south.
  - Corner 14: Established midway and on line between corners 1314.45 ft. north and south.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner I6: Set 1" I.D.x32" iron pipe with 4" alum. cap.  
7" Maple S66E 31.7 ft. 1/4S,NBT  
7" Maple N03E 45.8 Ft. 1/4S,NBT
  - Corner 7: Set 1" I.D.x36" iron pipe with 4" alum. cap.  
5" Sugar N58E 34.5 ft. 1/16S,BT  
8" Cherry S28E 52.9 ft. 1/16S,BT
  - Corner 14: Set 1" I.D.x32" iron pipe with 4" alum. cap.  
12" Aspen N20E 35.6 ft.  
Painted "X" on rock outcrop west 63.5 ft. NE leg power trans. tower S20W 133 ft.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_


(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-22-81

CHIEF OF SURVEY PARTY  
*Keith L. Sackett*  
MICHIGAN REGISTERED LAND SURVEYOR  
Keith L. Sackett  
Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006