

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Dickinson  
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T 41N R 30W	M2
	T 41N R 30W	L1
	T R	
2. Property Controlling In Section	T R	
	S 1 T 41N R 30W	7
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Stephen J. Szyszkoski, in a field survey on August 26, 1992, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereto as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

- (M2) Quarter corner common to Section 1 T41N-R30W and Section 6 T41-R29W. Original corner established by U.S. Deputy Surveyor Wm.A. Burt, 1849. Original BTs: Cedar 8 S62E 02, Pine 16 N10W 11. Found no subsequent record.  
 (L1) Quarter corner common to Section 1 T41N-R30W and Section 36 T42N-R30W. Original corner established by U.S. Deputy Surveyor Wm.A. Burt, 1849. Original BTs: Hemlock 4 N70E 24, Y. Birch 5 N75W 21. Found no subsequent record.  
 (7) North 1/16 corner between Section 1 T41N-R30W, and Section 6 T41N-R29W. Corner not established in original survey. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (M2) Original post and accessories not recovered. Found no acceptable evidence on the ground of the original corner position. Reestablished the corner by single proportionate measurement to the original record between the recorded section corner 2657.17' south and the recorded township corner 2568.15' north. From the position thus determined, I found a 1" pipe capped with a brass tablet stamped to show four quadrants, probably placed by Hanna Mining Co. engineers, bearing S10E, 16.93'. This corner appears to have been placed at 2640' north of the section corner, and I did not accept it.  
 (L1) Original post and accessories not recovered. Found corner monumented by a 1.5" dia. drill rod 0.13' west and 0.05' south of the single proportionate position between adjacent section corners. Accepted this monument as a careful and faithful reestablishment of the position of the original corner.  
 (7) Established corner at 20 chains proportionate measure north of the quarter corner common to Section 1 T41N-R30W and Section 6 T41N-R29W, on a straight line between recorded corners 1328.58' south and 1239.57' north. From the corner position, I found a 1" pipe with a brass cap, stamped into quadrants, probably placed by Hanna Mining Co. engineers, S02E, 25.05'. The Hanna monument appears to have been set at 1320' north of a similar monument near the quarter corner. I did not accept either of these Hanna monuments as marking the position of their respective corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |  |  |  |
|--|--|--|
| (M2) Placed a 1"x30" iron pipe capped with a 4" dia. cast aluminum MDRB tablet. Blazed and scribed the following new bearing trees:<br>5" Cedar S21E 26.7' (1/4S HBT)<br>15" W. Pine S74W 60.9' (1/4S HBT)<br>20" W. Pine N75W 57.8' (1/4S HBT)<br>Found 10" Hemlock with overgrown blaze facing the corner S10E 32.9'.<br>Placed a 3/4" pipe, projecting 6 ft., North 0.9'. | (L1) Found 1 1/2" dia. drill rod in clearing for power line. Blazed and scribed the following new bearing trees:<br>8" Sugar S70W 79.0' (1/4S HBT)<br>8" Sugar N01E 71.8' (1/4S HBT)<br>10" Sugar S01E 19.7' (1/4S HBT)<br>Set a measuring spike and plastic cap in NW face of the Northeastly of 2 power poles, S12W 47.51'.<br>Placed 3" squared elm post South, 1 ft. | (7) Placed a 1"x30" iron pipe capped with a 4" dia. cast aluminum MDRB tablet. Blazed and scribed the following bearing trees:<br>6" Sugar N35W 21.2' (1/16S HBT)<br>3" Sugar N20E 14.4' (1/16S HBT)<br>6" Sugar S40E 4.6' (1/16S HBT)<br>5" Sugar N04W 29.0' (1/16S HBT)<br>Set a 3/4" pipe projecting about 6 ft. northeast of the corner. |
|--|--|--|

Signed by Stephen J. Szyszkoski Date 1-12-93  
 Surveyor's Michigan License No. 33986

