

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson
 (County)

Located In:

Corner Code #

1. Public Land Survey	T <u>41N</u> R <u>30W</u>	<u>J6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>23</u> T <u>41N</u> R <u>30W</u>	<u>4</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 21 2000

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (J6) Center of Section 14. Corner not established in the original survey.
 (4-Sec. 23) Northwest 1/16 corner, Sec. 23. Corner not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J6) Established the corner at the intersection of straight lines connecting opposite 1/4 corners and monumented same with a 1" IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.
 (4-Sec. 23) Established the corner at the intersection of straight lines connecting opposite 1/16 corners and monumented same with a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J6) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following: 10" W. Pine N50E 27.0' "C1/4 BT" 23" R. Pine S04W 13.2' do 21" W. Pine N57W 25.8' do 8" Twin Cedar N27W 38.9' do 7" Maple, sq'd, N21E 2.7' to center. Corner set in 2'x2.8'x2' high rock mound. Bearings are magnetic. Dist. to notch in lower blaze, unless noted.	(4) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following: 16" W. Pine N21E 76.6' "1/16S BT" 5" Twin Sugar N83E 66.1' do 9" Sugar S45E 30.9' do 9" Sugar S75W 6.2' do Sq'd post adjacent. Mon. is set in 2' x 2'x1' high rock mound. Bearings are magnetic. Distances are to notch in lower blaze.
---	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/22/00

For the Michigan Department of Natural Resources - Forest Management Division