

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|-----------|
| 1. Public Land Survey | T <u>41N</u> R <u>30W</u> | <u>K5</u> |
| | T <u>41N</u> R <u>30W</u> | <u>I6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 28 2000

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2		1		
3													
4		7	8		9		10		11		12		
5													
6		18	17		16		15		14		13		
7													
8		19	20		21		22		23		24		
9													
10		30	29		28		27		26		25		
11													
12		31	32		33		34		35		36		
13													


A. Description of original monument and accessories and/or subsequent restoration:
 (K5) Section corner common to 11-12-13-14. Reestablished and recorded in 1953 by D.C.DeLaMater and recorded in 1993 by the undersigned. Found 1" pipe with 4" brass cap. 12" Maple S07W 60.3', 4" Balsam S50W 45.5', 4" Maple S64W 34.5'.
 (I6) Quarter corner common to Sections 14-15. Reestablished in 1981 by K.L.Sackett, RLS, by single proportionate measurement between section corners 2628.90' N and S. 1"IDx32" iron pipe with 4" alum. cap. 7" Maple S66E 31.7', 7" Maple N03E 45.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K5) The 1953 monument was recovered at record bearing and distance from the 1993 witnesses. The 1993 balsam is now a dead 6' high stub. The maples are in good condition with scribing visible. Left the monument in place and marked two new witnesses as described below.
 (I6) Recovered the 1981 monument as described, in good condition, and at record bearing and distance from the 1981 witnesses, both alive with overgrown blazes. Verified the position of the monument with respect to the section corners and accepted same as a careful and faithful reestablishment of the position of the original corner. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the

(K5) Found 1" pipe with 4" brass cap. Blazed and scribed the following: 4" Maple S27W 51.1' "S14 NBT" 3" Maple N83E 64.3' "S12 NBT" The 1993 wits: 14" Maple S07W 60.3' scribing visible 6" Maple S64W 34.5' do Sq'd spruce post adjacent. Bearings are magnetic. Distances to notch in lower blaze.	(I6) Found 1" pipe with 4" MDNR cap. Blazed and scribed the following: 6" Sugar S22E 31.5' "1/4S NBT" 14" Maple West 99.2' do The 1981 wits: 11" Maple N07E 45.8' ovrgwn blazes 10" Maple S64E 31.5' do Bearings are magnetic. Distances to notch in lower blaze.
--	---



Signed by Stephan J. Szyszkoski Date 8/22/00
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division