

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|-----------|
| 1. Public Land Survey | T <u>41N</u> R <u>30W</u> | <u>18</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 28 2000

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (18) Quarter corner common to 22-23. Established in 1849 by John Burt. "North between 22&23...40.00 Set Hemlock 1/4 sect. post. Sugar 20 N46E 10, Sugar 8 S30W 17...80.00 Sect. cor." Corner shown on surveys by James Moore, PS, 1984 and 1998. 1998 survey states: "Found 1" pin flush with ground. PP#74-2902 N30E 10.67, 4" Aspen S30E 23.23', 8" Aspen S67W 10.90', 8" Aspen N13W 26.11, Center Scott Dr. North 43.0'. This monument also used by R.F.Perkins, RLS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(18) Original post and accessories were not recovered. Found a 1" iron pin, set flush, at record bearing and distance from Moore's 1998 witnesses. Accepted the pin as the best available evidence of the position of the original corner. This pin is consistent with monumentation by R.F.Perkins, found along the E-W 1/4 line, Section 23. I found this monument to be 5.4' West and 5.7' South of MPOL between Dickinson Co. monument at Sec. cor. to north and Kimberly-Clark monument at Sec. cor. to South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(18) Found 1" iron pin.
 Fd. nail/tag in PP#74-2902 N30E 10.7'
 Fd. nail/tag in 7" Poplar S32E 23.2'
 Fd. nail/tag in 5" Poplar S66W 10.9'
 W'y PP guy anchor at grnd N42W 13.4'
 C/L Scott Dr. North 43'
 Set squared cedar post adjacent.
 Bearings are magnetic. Distances horizontal.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/22/00

For the Michigan Department of Natural Resources - Forest Management Division