

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
**7 Dickinson**

	Located in:	Corner Code //
1. Public Land Survey	T 42N R 27W	A2
	T R	D1
	T R	
	T R	
2. Property Controlling in Section	S 6 T R	1
	S T R	14
3. Miscellaneous Property in Sec	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat  
 5. Private Claims

I, Keith Sackett, in a field survey on June 24, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration

A2	D1	1	14
Original monument and accessories not found. Found old post bottom.	Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A2	D1	1	14
Restored at old post bottom which fits within 3 feet of proportion.	Restored midway and on line.	Established by proportion.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A2	D1	1	14
Set 1" x 32" iron pipe with 4" aluminum cap. 10" sugar N55E 6.2' 1/4s NBT 7" sugar N73W 7.0' 1/4s NBT 7" sugar S31W 30.0' 1/4s NBT 8" sugar S20E 8.0' 1/4s NBT	Set 1" ID x 36" iron pipe with 4" aluminum cap. 5" sugar S50E 67.5' 1/4s NBT 5" sugar S50W 67.2' 1/4s NBT In open little field.	Set 1" ID x 32" iron pipe with 4" aluminum cap. 7" sugar S75W 12.8' 1/16s BT 4" sugar S37E 13.8' 1/16s BT 6" yellow birch N06E 8.3' 1/16s BT 5" sugar N49W 21.8' 1/16s BT	Set 1" x 32" iron pipe with 4" aluminum cap. 7" sugar N81W 4.6' 1/16s BT 7" sugar East 21.0' 1/16s BT 6" sugar S05E 10.0' 1.16s BT

Signed by Keith L. Sackett Date July 1, 1991

Surveyor's Michigan License No. 19006

