

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T 42N R 27W	B1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 5 T R	2
	S 6 T R	2
3. Miscellaneous Property in Sec	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on June 24, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	18	20	21	22	23	24						
9												
10	30	28	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


B1	5-2	6-2
Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B1	5-2	6-2
Restored by proportion.	Established midway and on line.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B1	5-2	6-2
Set 1" ID x 30" iron pipe with 4" aluminum cap.	Set 1" ID x 36" iron pipe with 4" aluminum cap.	Set 1" ID x 32" iron pipe with aluminum cap.
12" sugar N69W 28.0' 1/4s NBT	7" cedar S25W 22.7' 1/16s BT	10" sugar N37W 21.3' 1/16s BT
14" sugar S20W 9.2' 1/4s NBT	10" cedar S59E 45.2' 1/16s BT	6" sugar S52E 19.7' 1/16s BT
7" sugar N05E 11.9' 1/4s NBT	5" spruce N66E 9.9' 1/16s BT	16" sugar N14E 23.2' 1/16s BT
12" yellow birch N82E 9.7' 1/4s NBT	4" spruce N57W 6.6' 1/16s BT	10" sugar S75W 38.7' 1/16s BT



Signed by Keith L. Sackett Date July 1, 1991

Surveyor's Michigan License No. 19006