

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
1 Dickinson
 (County)

	Located In:	Corner Code <u>77</u>
1. Public Land Survey	T <u>42N</u> R <u>27W</u>	
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S <u>6</u> T _____ R _____	<u>9</u>
	S _____ T _____ R _____	<u>10</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	<u>11</u>
	S _____ T _____ R _____	<u>13</u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on June 27, 19 91, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	•	•	•	5	4	3	2	1				
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	16	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

9	10	11	13
Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

9	10	11	13
Established midway and on line.	Established midway and on line.	Established during section subdivision.	Established during section subdivision.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

9	10	11	13
Set 1" ID x 32" iron pipe with 4" aluminum cap.	Set 1" ID x 32" iron pipe with 4" aluminum cap.	Set 1" ID x 32" iron pipe 1/4" aluminum cap, center of SW 1/4.	Set 5/8" x 2" re-bar with plastic cap in cedar post.
4" spruce N48W 6.3' 1/16s BT	5" spruce N68E 12.3' 1/16s BT	24" cedar S40E 13.7' 1/16s BT	12" cedar N32W 27.1' 1/16s BT
4" spruce S41W 18.6' 1/16s BT	6" spruce S80E 15.3' 1/16s BT	5" sugar S50W 23.4' 1/16s BT	14" cedar S64W 11.0' 1/16s BT
10" sugar S53E 22.0' 1/16s BT	4" spruce S50W 9.4' 1/16s BT	4" sugar N21W 4.7' 1/16s BT	10" cedar S44E 27.0' 1/16s BT
5" spruce N80E 30.1' 1/16s BT	6" aspen W20E 2.1' squared	7" sugar N75E 12.2' 1/16s BT	12" yellow birch N19E 44.2' 1/16s BT

Signed by Keith Sackett Date _____
 Surveyor's Michigan License No. 19006

