

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
T Dickinson

	(County)	Located In:	Corner Code #
1. Public Land Survey		T 42N R 27W	A3
		T R	B2
		T R	
		T R	
2. Property Controlling in Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Keith Sackett, in a field survey on June 27, 19 91, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A3	B2
Found cedar post, stumps that fits original bearing tree's	Not set on original survey nor subsequently, apparently.
10" cedar S27E 15 lks & 10" cedar N72W 13 lks.	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A3	B2
Restored at cedar post.	Established at intersection of 1/4 lines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A3	B2
Set 1" ID x 32" iron pipe with 4" aluminum cap.	Set 1" ID x 32" iron pipe with 4" aluminum cap.
5" cedar S82E 6.1' S7 NBT	12" sugar N85E 16.0' 1/4s BT
5" cedar N39E 21.8' S6 NBT	10" sugar S79W 25.4' 1/4s BT
7" cedar N47W 9.5' S1 NBT	9" sugar S02E 15.2' 1/4s BT
5" cedar S23W 8.3' S12 NBT	10" sugar N 42W 13.7' 1/4s BT

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

Signed by Keith Sackett Date \_\_\_\_\_  
Surveyor's Michigan License No. 19006

