

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	<u>DICKINSON COUNTY</u> LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. <u>X</u> R. <u>27</u> W.	I-5
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 17, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Section Corner 10, 11, 14, & 15, T42N, R27W
 1" iron pipe with 4" brass cap, set by D. Delamater, R.L.S. on 10-8-1952
 Cedar 10 S21W 21 lks. by Delamater
 Cedar 6 N18E 12 lks. by Delamater

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Re-witnessed the monument set by Delamater, because one of his NBT's is partially wind-thrown and the other nearly dead. Monument was set from an original BT in 1952, which at time was reported in place and in good condition. A cursory search for it by the undersigned on 7-17-78 revealed no recognizable trace of it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" I.D. x 48" iron pipe with 4" brass cap (by Delamater)
 Cedar 6 S65 1/2°E (mag.) 21.1 ft. "S14, NBT"
 Cedar 7 N16°W (mag.) 18.1 ft. "S10, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 1979
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

