

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

42 N R 27 W
T 43 N NR 27 W

Dickinson

COUNTY

DESCRIPTION OF CORNER Section corner common to sections 32 and 33, T43N R27W and sections 4 and 5, T42N R27W

DESCRIPTION OF CORNER MONUMENT 1" pipe and 4" brass cap

WITNESSES TO CORNER Cedar 14" N 80 E 49 links

Cedar 12" N 86 W 51 1/2 links


DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from 2 original cedar bearing trees, 1 still green. Scribe marks very plain on both trees.

Corner was found while cruising timber in this area.

Corner was placed and witnessed on 21 May 1956

SURVEYORS SEAL



SIGNED Henry S. Peterson
REGISTERED LAND SURVEYOR

DATE 5/25/56