MICHIGAN DEPARTMENT OF CONSERVATION

FORESTRY DIVISION

LAND CORNER RECORD

T 42 NR 27 W

| | | | Dickinson |
|-------------|----|--------|--|
| | | | COUNTY |
| DESCRIPTION | OF | CORNER | 1/4 corner between sections 6 and 7 |
| DESCRIPTION | OF | CORNER | MONUMENT 1" pipe with 4" brass cap |
| WIT TNESSES | то | CORNER | Cedar 12" S 85 E 13 links, marked 1/4 S NBT |
| | | | Cedar 16" N 53 W 28 links, marked 1/4 S NBT |
| | | | Cedar 5" S 64 W 32 links, marked 1/4 S NBT |
| | | | Distances measured from center of brass cap to NBT notch |

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from two original tamarack bearing trees, one in excellent condition and one ig good condition.

Corner was found while cruising timber in this area.

Corner was placed and witnessed on 25 April 1957 with Clarence R. Ryberg.

SURVEYORS SEAL

Henry G. Viterson

SIGNED Henry S. Peterson

REGISTERED LAND SURVEYOR

DATE 4/26/57