

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 NR 27 W

Dickinson

----- COUNTY

DESCRIPTION OF CORNER Section corner common to sections 5, 6, 7 and 8

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER Cedar 10" N 65 E 15 links, marked S 5 NBT

Cedar 13" S 66 W 29 links, marked S 7 NBT

Cedar 9" N 73 W 39 links, marked S 6 NBT

Distances measured from center of brass cap to NBT notch

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from two original cedar bearing trees, down, in fair condition. Found face and axe marks on both and scribe mark on one. Two old wood posts and piece of flange iron in place.

Corner was found while cruising timber in this area.

Corner was placed and witnessed on 25 April 1957 with Clarence R. Ryberg.

SURVEYORS SEAL

Henry S. Peterson

SIGNED Henry S. Peterson
REGISTERED LAND SURVEYOR

DATE 4/26/57